



# CHENNAI METROPOLITAN WATER SUPPLY & SEWERAGE BOARD

TENDER NO: CMWSSB/CNT/WSS/ICB/JICA/DESAL/CP01/018/2020-21

### LOAN AGREEMENT NO. ID-P267 JICA FUNDED PROJECT

#### **BIDDING DOCUMENT**

#### **FOR**

# PROJECT FOR CONSTRUCTION OF CHENNAI SEAWATER DESALINATION PLANT (I)

#### **PART-IV**

(PRICE SCHEDULE)

PROCUREMENT OF DESIGN/ENGINEERING, CONSTRUCTION, COMMISSIONING OF 400 MLD SEAWATER REVERSE OSMOSIS (SWRO) DESALINATION PLANT AT PERUR, CHENNAI WITH 20 YEARS OF OPERATION AND MAINTENANCE (DBO BASIS)

#### INTERNATIONAL COMPETITIVE BIDDING

PROJECT MANAGEMENT CONSULTANTS
SMEC International Pty Ltd.
NJS Engineers India Pvt. Ltd.
Tata Consulting Engineers Ltd.
SMEC India Pvt. Ltd.

SUPERINTENDING ENGINEER (CONTRACTS & MONITORING) CHENNAI METROPOLITAN WATER SUPPLY & SEWERAGE BOARD

**Date of Issue of Bidding Document:** xx/xx/2021

## **DOCUMENT CONTROL**

Document:	Bidding Document for Chennai 400 MLD Desalination Plant (CP1) at Perur
File Location:	
Project Name:	Project for Construction of Chennai Seawater Desalination Plant (I)
Revision Number:	9

## **REVISION HISTORY**

Revision No.	n No. Date Prepared by		Reviewed by	Approved for Issue by
9	Dr.Ghulam Mustafa Mr.Santosh Biswa		Mr.Abdel Fattah Toukan & PMC team	Dr.P.Dharmabalan

## **ISSUE REGISTER**

Distribution List	Date Issued	Number of Copies
CMWSSB	25 June 2021	1

## PMC DETAILS

	Dr.Ghulam Mustafa,  Desalination Expert – International Expert	Signature:	lenstafa			
Prepared by:	Mr.Santosh Biswa, Contract Management Specialist	Signature:	S. Bisna			
Reviewed by:	Mr.Abdel Fattah Toukan Contract Specialist (International Expert)	Signature:	J. Toukan			
Approved by:	Dr.P.Dharmabalan, Project Manager – International Expert	Signature:	P. Sharmablen.			
	PMC for Chennai Perur 400 MLD Desalination	Project office				
Address:	A, 13th Floor, Puravankara Primus, No.236 Okkiyampet, Old Mahabalipuram Road,					
	Thuraipakkam, Chennai 600 097, Tamil Nadu, India					
Tel:	+91 95607 02631 & +61419765881					
Email:	P.Dharma@smec.com	Smec.com Website: <u>www.smec.com</u>				

The information within this document is and shall remain the property of: SMEC and its project partners.

#### PREAMBLE TO PRICE SCHEDULE

- 1. This Price Schedule shall be read in conjunction with Instructions to Bidders and Bidding Documents, as listed in Sub-Clause 6.1 of Instructions to Bidders.
- 2. This Contract is a lump sum priced Contract, adjusted by the Variations and Adjustments detailed in Clause 13 of Particular Conditions of Contract, Part III. The Works are divided into Schedules each representing one or more groups of interrelated works forming part of the Works. These Schedules shall cover the full compensation of the Contractor for surveys, investigations, designs, drawings, documentations, construction, manufacture, supply, installation, erection, commissioning, tests for issue of Commissioning Certificate, defect liability, operation and maintenance during the Operation Service Period etc. The scope of work shall be in strict conformity with this Contract Documents.
- 3. The individual item descriptions and quantities within each Schedules of the Works included in this Contract are indicative only and shall not be taken as defining the scope of work to be executed under the Contract.
- 4. The item descriptions, if given, are general summary only, therefore any omission from, or error in, item descriptions within this Price Schedule shall neither warrant any adjustment to the Contract Price nor entitle the Contractor to seek an extension of time under the Contract.
- 5. Omissions in quoting the rate/amount against any item (s), leaving space/blank or amount unfilled, will be considered to be included in the other items and rate for such items will be treated as "Zero" and work will be required to be executed accordingly by the bidder. Any bidders doing so shall do at its own risks and costs.
- 6. The Base Price mentioned in each Schedule shall exclude GST only but shall include all costs on materials, duties, landing charges, shipping costs for transport by air, sea or land (or any combination thereof), insurance, import taxes, customs duties, loading, unloading, storage, getting into position, hoisting, lowering, distributing to positions, fixing, labour, setting-out, scaffolding and staging, plant, supervision, profit, overhead charges, all tests including commissioning test etc., making good prior to handing over to the Employer and anything reasonably to be inferred from the description of the item and indispensably necessary thereto.
- 7. The cost of the items for civil, mechanical, electrical, instrumentation and other related works shall be rational representing actual cost of the items. Bidders shall not load the cost of the items in a particular schedule to elsewhere in another schedule.
- 8. Each Schedule shall be deemed to be inclusive of all the Contractor's obligations to execute the part of the Works covered by the Schedule and to perform all his obligations under the Contract in respect thereof. Additional rows have been provided or inserted in each Schedules to include additional items to be executed to complete the works fully to operate

the plant smoothly. The Contractor shall not be entitled to receive any payment other than those mentioned above.

9. Following are the Schedules:

Schedule No. 1: Surveys & Investigations, Design, Drawings and Documentation

Schedule No. 2: Intake and Outfall Pipeline Works

Schedule No. 3: Civil Works

Schedule No. 4: Mechanical Works

Schedule No. 5: Electrical and Instrumentation, Control and Automation (ICA) Works

Schedule No. 6: Miscellaneous Works

Schedule No. 7: Process Proving

Schedule No. 8: Summary of CAPEX Price

Schedule No. 9: Operation & Maintenance Price

Schedule No. 10: Summary of Operation & Maintenance Price

Schedule No. 11: Grand Summary (Summary of CAPEX Price + Summary of Operation & Maintenance Price)

Schedule No. 12: Chemical Laboratory Items

Schedule No. 13: Workshop Items

Schedule No. 14: Chemical Consumption during Operation & Maintenance Period

Schedule No. 15: Manpower during Operation & Maintenance Period

Schedule No. 16: List of Asset Replacement and Spare Parts over 20 years

Schedule No. 17: List of Membrane Replacement over 20 years

Schedule No. 18: Payment Terms

- 10. The Bidder shall quote the respective prices against the items in the Schedules (1-17) and provide the soft copy (.pdf or .xls or .xlsx format only) and hard copy.
- 11. If the Bidder is a JV, the JV agreement should be registered in Chennai as per the prevailing registration act to the condition of registration department after award of the Contract. The cost towards the JV registration shall be borne by the Contractor.

#### **DECLARATION SHEET**

I, the undersigned, certify that all the data furnished in Part-IV, Price
Schedule and information pertaining to Part-I, Part-II and Part-III are correct and representation of
the offer covered by our Bid No dated I hereby certify that I am the
duly authorized representative of the Bidder whose name appears above my signature.
Bidder's Name
Authorized representative's Signature
Authorized representative's Name
Bidder's Intent:
The Bidder hereby agrees to comply with the requirements and intent of the Bidding Document for
the price indicated in this Price Schedule.
Seal of Company
Signature of the Bidder
Name & Address of the Bidder
Date :

\*Note: In case of consortium all the members should sign their bid proposal.

## **Summary of the Contract Price**

Item Description	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
	1	2	3
Schedule No. 1: Surveys & Investigations, Design, Drawings and Documentation (A)			
Schedule No. 2: Intake and Outfall Pipeline Works (B)			
Schedule No. 3: Civil Works (C)			
Schedule No. 4: Mechanical Works (D)			
Schedule No. 5: Electrical and Instrumentation, Control and Automation (ICA) Works (E)			
Schedule No. 6: Miscellaneous Works (F)			
Schedule No. 7: Process Proving (G)			
Schedule No. 8: Summary of CAPEX Price (H=A+B+C+D+E+F+G)			
Schedule No. 10: Summary of Operation & Maintenance Price (I)			

Item Description	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
	1	2	3
Grand Summary (Summary of CAPEX Price + Summary of Operation & Maintenance Price) (J=H+I)			
GST Amount @ 12% (K=J*12%)			
Provisional Sums (L)	INR 600,000,000		
Grand Total (M=J+K+L)			

Signature of Bidder:
Name and Designation:
Place:
Date:
Date

Company Name and Seal

## Schedule 1: Surveys & Investigations, Design, Drawings and Documentation

The total price of the Schedule No. 1 should not exceed 1.50% of the sum of prices from Schedule 2 to Schedule 7.

This Schedule shall include, but not limited to, the following items to deliver the project fit for purpose.

Item No.	Item Description	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
1.1	Survey, Process, Design and Drawings		1	2	3
1.1.1	Site survey, Bathymetric study, brine diffusion study, Subsoil investigations and Baseline Environmental monitoring	LOT			
1.1.2	PFD, Mass balance, Process design calculations and P&IDs	LOT			
1.1.3	Site layout plan, General arrangement drawings, Hydraulic diagram, Architectural drawings and Site grading plan	LOT			
1.1.4	Site drainage, Yard piping, Ext. plumbing etc.	LOT			
1.1.5	Single line diagrams, Substations and Electrical drawings	LOT			
1.1.6	Instrumentation & Control Systems	LOT			
1.1.7	Functional Design Specification (FDS)	LOT			
1.1.8	Ancillary Works	LOT			
1.1.9	Any other works, as required (Items should be specified)	LOT			
	Sub-Total Item No. 1.1 (Sum of Item 1.1.1 to 1.1.9)				
1.2	Civil Structural Designs and Drawings				
1.2.1	Intake and Outfall structures including headers and diffusers	LOT			
1.2.2	Intake Pumping station including band screen and pumps	LOT			
1.2.3	Pre-treatment Chemical Buildings + Tanks Storage area	LOT			
1.2.4	Flash mixing and flocculation	LOT			

Item No.	Item Description	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
1.2.5	Lamella Settlers	LOT	1	2	3
1.2.6	DAFs DAFs	LOT			
1.2.7	DMFs, Backwash tanks and Pump houses	LOT			
1.2.8	RO Buildings and ancillary structures	LOT			
1.2.9	RO Chemical Buildings	LOT			
1.2.10	Permeate tanks and Neutralization tanks	LOT			
1.2.11	Remineralization buildings and associate system	LOT			
1.2.12	Product Water Tanks	LOT			
1.2.13	Clear Water Tank	LOT			
1.2.14	Post Treatment Chemical Buildings	LOT			
1.2.15	Waste Sludge Balancing Tank with pumping system	LOT			
1.2.16	Gravity Thickeners	LOT			
1.2.17	Sludge Holding Tank and thickened sludge Pump House	LOT			
1.2.18	Sludge Treatment Building (BFP Building, along with polymer dosing systems and BFP feed pumping system)	LOT			
1.2.19	Administrative Building	LOT			
1.2.20	Control Building with Laboratory	LOT			
1.2.21	Warehouse and Workshop	LOT			
1.2.22	Sub Stations & Electrical buildings	LOT			
1.2.23	Firefighting and Security buildings	LOT			
1.2.24	Sewage treatment building	LOT			

Item	Item Description	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
No.	•		1	2	3
1.2.25	All yard piping at project site	LOT			
1.2.26	Ancillary works and any other works, as required (Items should be specified)	LOT			
	Sub-Total Item No. 1.2 (Sum of Item 1.2.1 to 1.2.26)				
1.2	Markania I Cartana Dariana and Darania an				
1.3	Mechanical System Designs and Drawings				
1.3.1	Intake Screen and Intake Pumps and Sluice gates	LOT			
1.3.2	Flash mixers, flocculators, tube settlers, valves, gates and dismantling joints at inlet structure, flocculation and Lamella Settlers				
1.3.3	Pumps, valves, gates, dismantling joints at DAF	LOT			
1.3.4	Backwash pumps at DMF	LOT			
1.3.5	Filter media, valves, gates, piping and underdrain system at DMFs	LOT			
1.3.6		LOT			
1.3.7	All mechanical equipment including valves, gates, dismantling joints at RO Feed Tank	LOT			
1.3.8	All mechanical equipment at RO system	LOT			
1.3.9	All mechanical equipment at RO chemical buildings	LOT			
1.3.10	All mechanical equipment at CO2 system	LOT			
1.3.11	All mechanical equipment at Limestone Filters	LOT			
1.3.12	All mechanical equipment at post treatment chemical buildings	LOT			
1.3.13	Valves, gates, dismantling joints at Product Water Tanks	LOT			

Item No.	Item Description	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
110.			1	2	3
1.3.14	Valves, gates, dismantling joints at CWR	LOT			
1.3.15	Sludge Balancing Tank with Submersible Pumps	LOT			
1.3.16	All mechanical equipment at Sludge Thickener	LOT			
1.3.17	All mechanical equipment at Thickened Sludge Holding Tank				
1.3.18	All mechanical equipment at Belt Filter Press including Feed Pumps	LOT			
1.3.19	Belt Filter Press and polymer dosing system	LOT			
1.3.20	Sludge conveyance system	LOT			
1.3.21	Sewage treatment system	LOT			
1.3.22	Ancillary works and any other works, as required (Items should be specified)	LOT			
	Sub-Total Item No. 1.3 (Sum of Item 1.3.1 to 1.3.22)				
1.4	Electrical Designs and Drawings				
	e e				
A	CP1 Plant Area				
1.4.1	Electrical & Mechanical Equipment Load Schedule	LOT			
1.4.2	Subgrade Earthing System, Potential Gradient Earthing System, Above Ground Earthing System, and Lightning Protection System Drawings	LOT			
1.4.3	Lighting Illumination Design Calculation in Buildings and Structures  Street Lighting Illumination Calculation	LOT			
	Area Lighting Illumination Calculation				

Item No.	Item Description	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
	Lighting and Small Power System Layout Drawings		_	<del>-</del>	
	Lighting and Small Power System Distribution Boards Drawings				
	Central Battery System Single Line Diagram and Control Schematic Drawings				
	Street Lighting System Layout Drawings				
	Street Lighting Feeder Pillar Single Line Diagram Drawing and Control Schematic Diagram Drawings				
1.4.4	FM 200 System Layout and Schematic Drawings	LOT			
1.4.5	UPS System Single Line Diagram Drawing and Control Schematic Diagram Drawing for Telecommunication & Data System, CCTV System, Fire Alarm System, FM200 System, Substation Automation System and SCADA System	LOT			
1.4.6	Electrical Cable Trench, Manholes and Cable Duct Bank Drawings Cable Route and Cable Tray Layout Drawings	LOT			
	,				
	Sub Distribution Board Load Schedules and Single Line Diagrams				
	Motor Control Centers Load Schedules and Single Line Diagrams				
1 4 7	Low Voltage Switchgear Load Schedules and Single Line Diagrams				
1.4.7	11kV Switchgear Load Schedules and Single Line Diagrams	LOT			
	Sub Distribution Board Panel Arrangement Drawings				
	Motor Control Centers Panel Arrangement Drawings				
	Low Voltage Switchgear Panel Arrangement Drawings				

Item No.	Item Description	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
	11kV Switchgear Panel Arrangement Drawings		1	2	3
В	230/110/11kV Gas Insulated Switchgear Substation				
1.4.8	Substation Subgrade Earthing System, Potential Gradient Earthing System, Above Ground Earthing System, and Lightning Protection System Drawings				
	230/110/11kV Substation Key Single Line Diagram Drawing				
1.4.9	230/110/11kV Substation Metering, Control, and Protection Schematic Diagram Drawings	LOT			
	Substation Automation System (IEC-61850) Architecture Drawing 230/110/11kV Substation General Arrangement Layout				
	Drawing				
	Substation 110V and 48V DC Batteries, Battery Chargers, and				
	DC Distribution Switchgear SLD and Control Schematic Diagram Drawings	LOT			
1.4.10	Substation 33/0.415kV Auxiliary Low Voltage AC Distribution	LOI			
	Switchgear Single Line Diagram and Control Schematic Drawings				
1 4 11	Substation Building and Civil Engineering Works including Sleeves and Openings Detail Drawings				
1.4.11	Substation Power Receiving Gantry Area Structural Works and Supports Structural Drawings				
	Substation Lighting, Emergency Lighting and Small Power				
	Layout Drawings.				
1.4.12	Lighting Illumination Design Calculation				
	Substation Data and Telecommunication System Drawings				
	Substation CCTV System Drawings				

Item No.	Item Description	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
	Substation FM 200 System Fire Protection Drawings Substation Fire Alarm System Drawings		_		
1.4.13	Deluge Water Spray System Drawings and Schematic Diagram for 150 MVA Power Transformers and 50 MVA Power Transformers				
	Substation Heating, Ventilation, and Air Conditioning System Drawings  Substation Potable Water System and Drainage System				
1.4.14	Drawings Substation Fiber Optic Multiplexer Equipment for Communication and Protection Control Schematic Drawings Substation SCADA System Drawing	LOT			
1.4.15	Substation EHV, HV, LV, and ELV Power, Control, Instrumentation, Automation, Telecommunication, Data, and SCADA System Cable Schedule Drawings	LOT			
1.4.16	Substation 150 MVA & 50MVA ONAN/ONAF Auto Power Transformer General Arrangement, Sections, and Elevation Drawings  Substation 150 MVA & 50MVA ONAN/ONAF Auto Power Transformer Automatic Voltage Regulation Control and Protection Schematic Diagram Drawing	LOT			
1.4.17	Substation 33/0.433kV 315 kVA & 11/0.433kV 315 kVAONAN Earthing Transformer Znyn11 General Arrangement Drawing  33kV & 11kV Outdoor Type Vacuum Circuit Breaker and Off Load Isolator for 315kVA Earthing Transformer Single Line Diagram, Protection and Control Schematic Diagram Drawings Neutral Earthing Resistor Single Line Diagram and Control	LOT			
	Schematic Diagram Drawing				

Item No.	Item Description	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
1.4.18	Substation Nitrogen Injection Fire Protection (NIFPS) System for 150 MVA ONAN/ONAF Auto Power Transformer and 50 MVA ONAN/ONAF Auto Power Transformer	LOT			
1.4.19	11kV Switchgear Single Line Diagram, Metering, Protection, and Control Schematic Diagram Drawings				
1.4.20	230/110/11/0.415kV Switchgears Load Flow Analysis, Short Circuit Calculations, Earthing Calculation, and Final Relay Coordination Settings (ETAP / CYME / SKM Software)  EHV, HV, LV Power Cable Sizing and Voltage Drop Calculations  Power Transformer and Earthing Transformer Load Sizing Calculations  11kV and 0.415kV Capacitor Bank Sizing Calculation	LOT			
1.4.21	Substation EHV, HV, LV, ELV Power, Control, Automation, Instrumentation, & SCADA Cable Route and Cable Tray Layout Drawings Substation Cable Trench, Manhole, Cable Duct Banks, and Sleeve Opening Drawings	LOT			
1.4.22	UPS System Single Line Diagram and Control Schematic Drawing for Substation Automation System, Telecommunication & Data System, Fire Alarm System, FM 200 System, Deluge Water Spray System, and CCTV System.	LOT			
1.4.23	Current Transformer and Voltage Transformer Sizing Calculation  110V and 48V DC Battery and Battery Charger Sizing Calculation	LOT			
1.4.24	Sub Distribution Board Panel Arrangement Drawings  Motor Control Centers Panel Arrangement Drawings	LOT			

Item	Item Description	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
No.	iciii Description	Omt	1	2	3
	Low Voltage Switchgear Panel Arrangement Drawings		_	<del>-</del>	
	33kV Switchgear and Isolator Outdoor Panel Arrangement Drawings				
	Neutral Earthing Resistor Panel Arrangement Drawing				
	230kV GIS Technical User Guide Manual and Data Sheets				
	110kV GIS Technical User Guide Manual and Data Sheets				
	150 MVA Power Transformer Technical User Guide Manual and Data Sheet				
	50 MVA Power Transformer Technical User Guide Manuals and Data Sheets				
	33kV Outdoor Type Circuit Breaker and Isolator Technical User Guide Manuals and Data Sheets				
	Metering and Protection Relays Technical User Guide Manuals and Data Sheets				
	Current Transformers and Voltage Transformers Technical User Guide Manuals and Data Sheets				
	230kV, 110kV, 33kV, 11kV XLPE Cables Technical User Guide Manual and Data Sheets				
	Low Voltage Power and Control Cables Technical User Guide Manual and Data Sheets				
	Fire Alarm System, FM200 System, Deluge Water Spray System Technical User Guide Manual and Data Sheets				
	Substation Fiber Optic Multiplexer Equipment for Communication and Protection Control Technical User Guide Manual and Data Sheets				
	Substation SCADA System Technical User Guide Manual and Data Sheets				
	Substation Automation System (IEC-61850) Technical User				

Item No.	Item Description	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
110.			1	2	3
	Guide Manual and Data Sheets CCTV System Technical User Guide Manual and Data Sheets				
	•				
	HVAC System Technical User Guide Manual and Data Sheets				
1.4.25	HVAC Cooling Load Calculation				
	Sub-Total Item No. 1.4 (Sum of Item 1.4.1 to 1.4.25)				
	Instrumentation, Control & Automation Drawings/	1			
1.5	Documents Control & Automation Drawings				
1.5.1	DCS System Architecture	LOT			
1.5.2	DCS Functional Specification	LOT			
1.5.3	Instrument Schedule	LOT			
1.5.4	DCS database IO List	LOT			
1.5.5	PLC System configuration/ Controller drawing	LOT			
1.5.6	Instrument control panel design drawings	LOT			
1.5.7	Instrument data sheets	LOT			
1.5.8	General Arrangement of PLC Panels	LOT			
1.5.9	PLC system Power & Control Schematics	LOT			
1.5.10	PLC system BOM	LOT			
1.5.11	DCS system graphic designs	LOT			
1.5.12	Block Logic Diagram	LOT			
1.5.13	PLC and DCS System FAT Procedure	LOT			

Part-IV: Price Schedule

Item No.	Item Description	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
			1	2	3
1.5.14	Instrument Cable Schedule	LOT			
1.5.15	GA of Junction Boxes	LOT			
1.5.16	GA of Pneumatic Control Boxes	LOT			
1.5.17	Field instrument layout drawings	LOT			
1.5.18	Instrument Hook ups	LOT			
1.5.19	Cable & Trench Layout Drawing	LOT			
1.5.20	FOC Core Allocation Diagram	LOT			
1.5.21	Control Room Layout & Equipment drawings	LOT			
1.5.22	Integrated Security System Specifications	LOT			
1.5.23	Integrated Security System Drawings	LOT			
1.5.24	Fire Alarm & Detection System Specification	LOT			
1.5.25	Fire Alarm & Detection System Drawings	LOT			
1.5.26	Central Control Room Drawings	LOT			
1.5.27	Any other works, as required (Items should be specified)	LOT			
	Sub-Total Item No. 1.5 (Sum of Item 1.5.1 to 1.5.27)				
1.6	As Built Drawing				
1.6.1	Civil & Building works	LOT			
1.6.2	Mechanical systems	LOT			
1.6.3	Electrical system	LOT			

Item			Base Price in Local	Base Price in Foreign	Base Price in Foreign
No.	Item Description	Unit	Currency (INR)	Currency (USD)	Currency (JPY)
1 6 4		I OTT	1	2	3
1.6.4	Control, Instrumentation & Automation system	LOT			
1.6.5	Any other ancillary system	LOT			
	Sub-Total Item No. 1.6 (Sum of Item 1.6.1 to 1.6.5)				
1.7	Other Documentation				
1.7.1	Process Design Basis Report	LOT			
1.7.2	Design Basis Report - Electrical	LOT			
1.7.3	Operation & Maintenance Manuals including Trouble Shooting	LOT			
1.7.4	Training Programme and Manuals	LOT			
1.7.5	Design and Process Details with excel sheets	LOT			
1.7.6	Standard Operating Procedures	LOT			
1.7.7	Any other documents as required	LOT			
	Sub-Total Item No. 1.7 (Sum of Item 1.7.1 to 1.7.7)				
1.8	Bidder shall list here details of additional items required for the complete plant design, drawing and documentation as per the Contract.  Sub-Total Item No. 1.8 (Sum of Items therein)				
	Total Schedule 1 (Sum of Sub-Totals of Item No. 1.1 to Item No. 1.8)				

Item No.	Item Description	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
	Total carried forward to Schedule No. 8				

Signature of Bidder:
Name and Designation:
Place:
Date:
Company Name and Seal

#### **Schedule 2: Intake and Outfall Pipeline Works**

This Schedule shall include, but not limited to the following items to deliver the works from supply to commissioning fit for the purpose as per the Contract.

Item No.	Item Description of Intake and Outfall Pipeline Items for Procurement, Supply, Installation/Erection, Testing and Commissioning for 2x200 MLD Plant		Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
			1	2	3
2	Intake and Outfall (400 MLD)				
2.1	Supply of 2500 mm OD twin HDPE pipelines and laying of pipelines for the length of 1150 m offshore each	Lot			
2.2	Supply and Fixing of Offshore Velocity Cap Type Heads (2 No.) with all allied works such as fish net, boulders, manholes, etc. at offshore intake. Two Screen made of Duplex Steel Frame and Cu-Ni Screen with 100 mm C/c opening	Lot			
2.3	Supply of 2500 mm OD HDPE pipelines and all works for laying of Outfall pipeline for the length of 750 m Offshore	Lot			
2.4	Supply and Fixing of Offshore Diffusers and all allied works at brine outfall. Diffuser made of Super Duplex Steel.	Lot			
2.5	Any other works to provide complete intake and outfall piping system (Items should be specified)	Lot			
	Total Schedule 2 (Sum of Item No. 2.1 to Item No. 2.5) Total carried forward to Schedule No. 8				

Signature of Bidder

Name & Designation

Company Name and Seal

#### **Schedule 3: Civil Works**

This Schedule shall include, but not limited to the following items to deliver the works from supply to commissioning fit for the purpose as per the Contract.

Item No.	Item Description for Supply, Construction, Testing and Commissioning of Civil Works for 2 x 200 MLD Plant	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
			1	2	3
3.1	Intake and Outfall Structures				
3.1.1	Supply, construction and commissioning of complete Intake Pumping Station including intake well, band screen area, pump area, discharge piping, flash mixer tank to flocculation system	Lot			
3.1.2	Supply, construction and commissioning of structures associated with Pigging System	Lot			
3.1.3	Supply, construction and commissioning of Outfall tank	Lot			
3.1.4	Any other civil works (Items should be specified)	Lot			
	Sub-Total Item No. 3.1 (Sum of Item 3.1.1 to 3.1.4)				
3.2	Shock Chlorination and Air Impingement System				
3.2.1	Supply, construction and commissioning of Building for shock chlorination dosing pumps, air compressors and air vessels with Hypochlorite storage tank.	Lot			
3.2.2	Any other civil works (Items should be specified)	Lot			
	Sub-Total Item No. 3.2 (Sum of Item 3.2.1 to 3.2.2)				
3.3	Chemical Building for Pre-treatment				
3.3.1	Supply, construction and commissioning of Chemical Building for pre- treatment with solution preparation tanks, dosing tanks area and storage area for solid chemicals and dosing pumps area for FeCl3, polymer, acid	Lot			

Item No.	Item Description for Supply, Construction, Testing and Commissioning of Civil Works for 2 x 200 MLD Plant	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
			1	2	3
	and hypochlorite, bunds, overhead service water tank etc. and other				
	facilities as required.				
3.3.2	Any other civil works (Items should be specified)	Lot			
	Sub-Total Item No. 3.3 (Sum of Item 3.3.1 to 3.3.2)				
3.4	Coagulation and Flocculation System				
	Supply, construction, and commissioning of Inlet-structure with baffles,	Lot			
3.4.1	flash mixing chambers with weirs, piping, valve & flowmeter chambers				
	and walkway, handrails etc. as applicable				
	Supply, construction and commissioning of Flocculation Chambers with	Lot			
3.4.2	hopper drain system, walkway platform, handrails etc. as per Contract and				
	complete in all respect.				
3.4.3	Any other civil works (Items should be specified)	Lot			
	Sub-Total Item No. 3.4 (Sum of Item 3.4.1 to 3.4.3)				
3.5	Lamella Settler				
	Supply, construction and commissioning of Lamella Clarifier with tube	Lot			
3.5.1	settlers, hoppers drain system, walkway platform, handrails, pipes, valve &				
	flowmeter chambers etc. as per Contract and complete in all respect.				
3.5.2	Any other civil works (Items should be specified)	Lot			
	Sub-Total Item No. 3.5 (Sum of Item 3.5.1 to 3.5.2)				
3.6	DAF				
	Supply, construction and commissioning of DAF structure and building	Lot			
3.6.1	along with tanks, pipes, valve & flowmeter chambers and complete system				
	as per the Contract.				
3.6.2	Any other works (Items should be specified)	Lot			

Item No.	Item Description for Supply, Construction, Testing and Commissioning of Civil Works for 2 x 200 MLD Plant	Unit	Base Price in Local Currency (INR)	Currency (USD)	Base Price in Foreign Currency (JPY)
			1	2	3
	Sub-Total Item No. 3.6 (Sum of Item 3.6.1 to 3.6.2)				
3.7	GDMF				
	Supply, construction and commissioning of GDMF structure and building	Lot			
3.7.1	along with media tanks, underdrain system, pipes, valve & flowmeter				
3.7.1	chambers, inlet channel, filtrate channel and complete system in all				
	respect as per the contract				
3.7.2	Any other civil works (Items should be specified)	Lot			
	Sub-Total Item No. 3.7 (Sum of Item 3.7.1 to 3.7.2)				
3.8	DMF Backwash and RO Feed Tank				
	Supply, construction and commissioning of DMF backwash and RO feed	Lot			
3.8.1	tank structures, pumps and blower chambers, RO feed pumping station,				
3.0.1	any other tanks and valve/flowmeter chambers along with structure as				
	needed.				
3.8.2	Any other works (Items should be specified)	Lot			
	Sub-Total Item No. 3.8 (Sum of Item 3.8.1 to 3.8.2)				
3.9	RO System				
	Supply, construction and commissioning of Industrial Steel Structures to	Lot			
3.9.1	inhouse RO system along with CIP system with chemical storage and				
	dosing system, MCC and all other areas as per the Contract.				
3.9.2	Supply, construction and commissioning of permeate tanks as per the	Lot			
3.9.2	Contract.				
3.9.3	Supply, construction and commissioning of neutralization tanks as per the	Lot			
3.7.3	Contract.				
3.9.4	Any other civil works (Items should be specified)	Lot			
	Sub-Total Item No. 3.9 (Sum of Item 3.9.1 to 3.9.4)				

Item No.	Item Description for Supply, Construction, Testing and Commissioning of Civil Works for 2 x 200 MLD Plant	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
			1	2	3
3.10	Chemical Building for RO System				
	Supply, construction and commissioning of Chemical Building with all	Lot			
3.10.1	chemical tanks and overhead service water tank and with sufficient area to				
	accommodate all the dosing system, bunds, drain etc. and all other features.				
3.10.2	Any other civil works (Items should be specified)	Lot			
	<b>Sub-Total Item No. 3.10 (Sum of Item 3.10.1 to 3.10.2)</b>				
3.11	Post Treatment System				
3.11.1	Supply, construction and commissioning of CO2 storage areas with all	Lot			
3.11.1	pipes, valve/flowmeter chambers and any other structure as needed.				
	Supply, construction and commissioning of RCC Limestone Filter	Lot			
3.11.2	structure with areas for limestone storage and feeding, all pipes,				
	valve/flowmeter chambers and any structure as needed.				
3.11.3	Any other civil works (Items should be specified)	Lot			
	<b>Sub-Total Item No. 3.11 (Sum of Item 3.11.1 to 3.11.3)</b>				
3.12	Chemical Building for Post Treatment				
	Supply, construction and commissioning of Chemical Building with all the	Lot			
3.12.1	post treatment chemical tanks and overhead service water tank and with				
3.12.1	sufficient area to accommodate dosing system, bunds, drain, etc. and all				
	other features.				
3.12.2	Any other civil works (Items should be specified)	Lot			
	<b>Sub-Total Item No. 3.12 (Sum of Item 3.12.1 to 3.12.2)</b>				
3.13	Waste /Sludge Treatment and Conveyance System				
3.13.1	Supply, construction and commissioning of Waste Sludge Balance Tank	Lot			
3.13.2	Supply, construction and commissioning of Gravity Thickeners	Lot			

Item No.	Item Description for Supply, Construction, Testing and Commissioning of Civil Works for 2 x 200 MLD Plant	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
			1	2	3
3.13.3	Supply, construction and commissioning of Thickened Sludge Holding tanks	Lot			
	Supply, construction and commissioning of Sludge treatment building	Lot			
3.13.4	(BFP building), with sludge feed pump area, chemical storage and dosing				
	areas and all other areas as required.				
3.13.5	Any other civil works (Items should be specified)	Lot			
	<b>Sub-Total Item No. 3.13 (Sum of Item 3.13.1 to 3.13.5)</b>				
3.14	Product Water Tanks				
3.14.1	Supply, construction and commissioning of Product Water Tanks with air HEPA filters and watertight cover lids	Lot			
3.14.2	Any other civil works (Items should be specified)	Lot			
	<b>Sub-Total Item No. 3.14 (Sum of Item 3.14.1 to 3.14.2)</b>				
3.15	Clear Water Reservoir				
3.15.1	Supply, construction and commissioning of RCC Clear Water Tank with air HEPA filters and watertight cover lids	Lot			
3.15.2	Any other civil works (Items should be specified)	Lot			
	<b>Sub-Total Item No. 3.15 (Sum of Item 3.15.1 to 3.15.2)</b>				
3.16	Electrical Building and MCC for complete plant				
3.16.1	Supply, construction and commissioning of substation building including Switchyard & Transformer area	Lot			
3.16.2	Supply, construction and commissioning of MCC Rooms for complete	Lot			
3.10.2	plant including Diesel Generator Room				
3.16.3	Any other civil works (Items should be specified)	Lot			
	<b>Sub-Total Item No. 3.16 (Sum of Item 3.16.1 to 3.16.3)</b>				

Itom No	Item Description for Supply, Construction, Testing and Commissioning of Civil Works for 2 x 200 MLD Plant	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
			1	2	3
3.17	Administration, Laboratory and Control Buildings				
1 3 1 / 1	Supply, construction and commissioning of Administrative building	Lot			
	including Canteen area and guest house	_			
	11 7	Lot			
	Any other civil works (Items should be specified)	Lot			
	<b>Sub-Total Item No. 3.17 (Sum of Item 3.17.1 to 3.17.3)</b>				
3.18	Warehouse and Workshop				
1 3 18 1	Supply, construction and commissioning of Ware-house – Industrial Steel Structure	Lot			
1 3 18 2	Supply, construction and commissioning of Workshop – Industrial Steel Structure	Lot			
3.18.3	Any other civil works (Items should be specified)	Lot			
	Sub-Total Item No. 3.18 (Sum of Item 3.18.1 to 3.18.3)				
3.19	Sewage Treatment Plant				
1 3 19 1	Supply, construction and commissioning of sewage treatment plant Building	Lot			
1 3.19.2	Supply, construction and commissioning of all tanks for the treatment plants	Lot			
3.19.3	Any other civil works (Items should be specified)	Lot			
	Sub-Total Item No. 3.19 (Sum of Item 3.19.1 to 3.19.3)				
3.20	Misc. Works at Site				
3.20.1	Supply, construction and commissioning of Parking lot, sign board, light, traffic signal, Site clearance, filling, removal of slurry to assigned quarry, temporary works etc., as specified	Lot			

Item No.	Item Description for Supply, Construction, Testing and Commissioning of Civil Works for 2 x 200 MLD Plant	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	
			1	2	3
3.20.2	Supply of material and Backfilling of the plant site to bring uniform ground	Lot			
	level at CD+6.50m excluding burial and area not included in the plant.	T -4			
2 20 2	Supply, construction and commissioning of RCC retaining wall up to CD				
3.20.3	+6.50m and min 2.50m high Brick wall boundary around the plant site and burial ground sites				
2 20 4	Supply, construction and commissioning of two Plant Gates and Security	Lot			
3.20.4	smart houses with cameras				
3.20.5	Firefighting building and associated structures				
3.20.5	Any other works (Items should be specified)	Lot			
	Sub-Total Item No. 3.20 (Sum of Item 3.20.1 to 3.20.5)				
3.21	Roads and Drainage				
3.21.1	Supply and Construction of all Roads and paths etc. as specified at per the	Lot			
3.21.1	plant layout				
3.21.2	Supply and Construction of Site storm water drainage system, both for the	Lot			
3.21.2	plant and burial grounds as required and Rainwater Harvesting structures.				
3.21.3	Plantation, Landscaping as specified	Lot			
3.21.4	All yard pipe works not covered above	Lot			
3.21.5	Supply, construction and commissioning of Firefighting Rooms for	Lot			
3.21.3	complete plant				
3.21.6	Any other works (Items should be specified)	Lot			
	Sub-Total Item No. 3.21 (Sum of Item 3.21.1 to 3.21.6)				
3.22	All area of the works required in Civil Supply, Construction works for				
J,22	the Desalination Plant as per the Contract Specifications				
	Sub-Total Item No. 3.22 (Sum of Items therein)				

Item No.	Item Description for Supply, Construction, Testing and Commissioning of Civil Works for 2 x 200 MLD Plant	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
	Total Schedule 3 (Sum of Sub-Totals of Item No. 3.1 to Item No. 3.22)				
	Total carried forward to Schedule No. 8				

Signature of Bidder

Name & Designation

Company Name and Seal

#### **Schedule 4: Mechanical Works**

This Schedule shall include, but not limited to the following items to deliver the works from supply to commissioning fit for the purpose as per the Contract.

Item No.	Item Description of Mechanical Items for Procurement, Supply, Installation/Erection, Testing and Commissioning for 2x200 MLD Plant	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
			1	2	3
4.1	Intake Pumping Station (400 MLD)				
4.1.1	On shore Travelling band screen with 3mm mesh (4 x 33%)	Lot			
4.1.2	Vertical Turbine Intake Sea Water Pumps (6W+3S) made of Super Duplex with PREN≥41 including Electric Motor (s) complete with intake, outlet and nonreturn valves, dismantling joints, piping etc.	Lot			
4.1.3	Pigging Systems complete in all respect for intake pipeline cleaning with pig launching and receiving system having two Pigs	Lot			
4.1.4	Isolation Gates (Duplex Steel) for Intake and Outfall tanks	Lot			
4.1.5	Shock chlorination for offshore Heads including tanks, injection system, pumps, piping, valves and all allied items.	Lot			
4.1.6	Compressed air system including compressors, pressure vessels, piping etc. complete in all respect for offshore Heads	Lot			
4.1.7	Any other works to provide the complete system in the intake pumping station area (Items should be specified)	Lot			
	Sub-Total Item No. 4.1 (Sum of Item 4.1.1 to 4.1.7)				
4.2	Pre-treatment Chemical Systems (2x200 MLD)				
4.2.1	98% Sulphuric Acid bulk Storage tanks: Cylindrical horizontal dished end carbon steel (IS 2062) tanks (2 tanks), internally ebonite Lined & externally coated with epoxy paint, complete with dosing tanks and dosing pumping system facility, transfer/unloading pumps, scrubbers, etc. and all other associated structures and features to complete the system.	Lot			

Item No.	Item Description of Mechanical Items for Procurement, Supply, Installation/Erection, Testing and Commissioning for 2x200 MLD Plant	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
	1 mit		1	2	3
4.2.2	GRP tanks for FeCl <sub>3</sub> and hypochlorite bulk storage (2 tanks for each chemical for total 1 month storage) with transfer/onloading pumps and scrubbers, and all other associated structures and features to complete the system	Lot			
4.2.3	Hypochlorite dosing system with pumps, valves, strainers, and equipment complete in all respect for automatic chemical dosing as per the contract	Lot			
4.2.4	FeCl <sub>3</sub> dosing system with pumps, agitators, valves, strainers, EOT crane and equipment complete in all respect for automatic chemical dosing as per the contract	Lot			
4.2.5	Polymer dosing system with pumps, agitators, valves, strainers, EOT, powder polymer transfer system using ejector and equipment complete in all respect for automatic chemical dosing as per the contract	Lot			
4.2.6	Any other works to provide the complete system (Items should be specified)	Lot			
	Sub-Total Item No. 4.2 (Sum of Item 4.2.1 to 4.2.6)				
4.3	Pre-treatment Process Units (2 x 200MLD)				
4.3.1	Coagulation and flocculation system including flash mixer, flocculator mixers complete with all associated piping and valves, gates, sludge disposal facility etc.	Lot			
4.3.2	Lamella Settlers including all associated piping and valves, gates, sludge disposal facility etc.	Lot			
4.3.3	Dissolved Air Floatation, complete with pressurized vessel, recycle pumps and all associated valves, pipes, sludge disposal facility etc. in totality	Lot			

Item No.	Item Description of Mechanical Items for Procurement, Supply, Installation/Erection, Testing and Commissioning for 2x200 MLD Plant	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
4.3.4	Gravity Dual Media Filtration, complete in totality including backwash pumps and blowers, and all associated valves and equipment required for its fully automated operations.	Lot			
4.3.5	Any other works to provide the complete system (Items should be specified)	Lot			
	Sub-Total Item No. 4.3 (Sum of Item 4.3.1 to 4.3.5)				
4.4	DMF Backwash and RO Feed Tank (2 x 200 MLD)				
4.4.1	DMF backwash and RO feed—tank - complete in totality including all valves and gates along with any equipment needed as per the Contract.	Lot			
4.4.2	Any other works (Items should be specified)	Lot			
	Sub-Total Item No. 4.4 (Sum of Item 4.4.1 to 4.4.2)				
4.5	RO Skids, Chemical Dosing and CIP System (2 x 200 MLD)				
4.5.1	Cartridge Filters including housing and complete with all valves and piping, drain, vents, plugs, foundation bolts, leg supports, static mixers etc. for complete requirement in RO system	Lot			
4.5.2	RO skids/trains including all items to complete the skids	Nos.			
4.5.3	Reverse Osmosis 8" membranes	Nos.			
4.5.4	Pressure Vessel for RO membranes including Super Duplex coupling.	Nos.			
4.5.5	Antiscalant, SMBS, Caustic Soda and any other chemicals bulk storage tanks and dosing Systems including tanks, pumps, valves, strainers, piping, EOT crane and all other equipment complete in all respect for automated chemical dosing.	Lot			

Item No.	Item Description of Mechanical Items for Procurement, Supply, Installation/Erection, Testing and Commissioning for 2x200 MLD	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
	Plant		1	2	3
4.5.6	RO Booster Pumps with Impeller, casing, shaft Super Duplex with PERN≥41. Motor, VFD complete with all piping and valves.	Nos.			
4.5.7	RO high pressure pumps with impeller, casing, shaft Super Duplex (2507) with PERN≥43. Motor, VFD complete with all piping and valves.	Nos.			
4.5.8	ERD Feed Pumps with Impeller, casing, shaft Super Duplex with PERN≥41. Motor, VFD (if required) complete with all piping and valves.	Nos.			
4.5.9	ERD Recirculation Pumps with Impeller, casing, shaft Super Duplex with PERN≥43. Motor, VFD (if required) complete with all piping and valves.	Nos.			
4.5.10	Energy Recovery Device –ERD) – pipe headers, flanges, U clamps, fasteners, Victaulic coupling for making connections complete in all respects including anchor foundation bolts etc.	Nos.			
4.5.11	Cleaning in Place (CIP) system complete in totality with heater, pumps, valves and piping etc. and all equipment needed for fully automated process.	Lot			
4.5.12	Any other works to provide the complete system (Items should be specified)	Lot			
	Sub-Total Item No. 4.5 (Sum of Item 4.5.1 to 4.5.12)				
4.6	Post Treatment System (2 x 200 MLD)				
4.6.1	Lime filters along with auto lime charging system including pipe, valves complete in all respect for auto operation	Lot			
4.6.2	Lime filters backwash pumping and blower system with pipe, valves complete in all respect for auto operation				

Item No.	Item Description of Mechanical Items for Procurement, Supply, Installation/Erection, Testing and Commissioning for 2x200 MLD Plant	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
4.6.3	CO <sub>2</sub> storage vessels	Lot			
4.6.4	CO <sub>2</sub> Dosing System comprising of CO <sub>2</sub> filter, Flow regulating valve, Automatic shut off valve, Manual shut off valve, Pressure reducing valve, Safety valves, Discharge valve, Limit switches, automatic change over planes, all mounted on a stainless-steel base frame CO <sub>2</sub> Flow meter System, Mass flow sensor (fully calibrated) assembled to process pipe. As per designed pipe size and pressure ranges.	Lot			
4.6.5	Caustic storage, dosing system with all tanks, pumps, valves, pipes, EOT and all equipment for auto chemical dosing	Lot			
4.6.6	Hypochlorite storage, dosing system with all tanks, pumps, valves, pipes, EOT and all other equipment for auto chemical dosing	Lot			
4.6.7	Any other works to provide the complete system (Items should be specified)	Lot			
	Sub-Total Item No. 4.6 (Sum of Item 4.6.1 to 4.6.7)				
4.7	Product Water Tanks, CWR and Outfall Tank	Lot			
4.7.1	Product Water Tanks, CWR and Outfall—Tank — all mechanical works complete in totality including all valves, gates, piping along with any equipment needed as per the Contract.	Lot			
4.7.2	Any other works to provide the complete system (Items should be specified)	Lot			
	Sub-Total Item No. 4.7 (Sum of Item 4.7.1 to 4.7.2)				
4.8	Waste /Sludge Conveyance and Treatment System				
4.8.1	Waste Sludge Balance–Tank - all mixer, submersible pumps, valves, static mixer etc.	Lot			
4.8.2	Gravity Thickeners - all mechanical system, including valves, pipes, rotating bridge with mixer and sludge scraping system,	Lot			

Item No.	Item Description of Mechanical Items for Procurement, Supply, Installation/Erection, Testing and Commissioning for 2x200 MLD Plant	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
4.8.3	Thickened Sludge Holding-tank - all mechanical system, including valves, pipes, mixer and BFP feed pumps	Lot			
4.8.4	BFP system - BFP units complete in all respect for auto operation producing 25% consistent solid chips.	Lot			
4.8.5	Chemical dosing system i.e., polymer for thickener and BFP complete in all respect.	Lot			
4.8.6	Any other works to provide the complete system (Items should be specified)	Lot			
	Sub-Total Item No. 4.8 (Sum of Item 4.8.1 to 4.8.6)				
4.9	Miscellaneous				
4.9.1	Mechanical works for Air Compressor, Air Conditioning & Ventilation System including Cooling tower etc. as required in all buildings and covered structures.	Lot			
4.9.2	Fire Detection and Protection System in all building and covered places. Fire Fighting vehicles, pumps, pipes and associated items.	Lot			
4.9.3	Maintenance Bay Equipment (EOT Cranes, Hoist & Monorails etc.) as needed in all buildings and Industrial structures	Lot			
4.9.4	Building Services including domestic water systems. The Bidder shall list here details of any additional items required for a complete installation	Lot			
4.9.5	Workshop equipment and other items	Lot			
4.9.6	Mechanical equipment at sewage treatment	Lot			

Part-IV: Price Schedule

Item No.	Item Description of Mechanical Items for Procurement, Supply, Installation/Erection, Testing and Commissioning for 2x200 MLD Plant	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
	I IUII		1	2	3
4.9.7	Other Miscellaneous Equipment / Items / System not mentioned above but as required in Employers Requirements in contract (Items should be specified)	Lot			
	Sub-Total Item No. 4.9 (Sum of Item 4.9.1 to 4.9.7)				
4.10	Bidders shall list here details of any additional items required for a complete system for smooth automatic operation of the 2x200 MLD desalination plant				
	Sub-Total Item No. 4.10 (Sum of Items therein)				
4.11	Building Services for water supply and other mechanical works requirements. The Bidder shall list below details of items required for a complete installation of all mechanical system at all buildings				
	Sub-Total Item No. 4.11 (Sum of Items therein)				
	Total Schedule 4 (Sum of Sub-Totals of Item No. 4.1 to Item No. 4.11)				
	Total carried forward to Schedule No. 8				

Signature of Bidder

Name & Designation

Company Name and Seal

### Schedule 5: Electrical and Instrumentation, Control and Automation (ICA) Works

This schedule shall include, but not limited to the following items to deliver the works from supply to commissioning fit for the purpose as per the Contract.

Item No.	Installation/Erection, Testing and Commissioning for 2x200 MLD		Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
	Plant		1	2	3
5.1	Intake and Outfall (400 MLD)				
5.1.1	All electrical works at Intake and Outfall system including but not limited to Chemical Dosing System Pumps, Screen Backwash Pumps, Trash Racks, Trash Rack Garbage Machine, Travelling Band Screen, LV Power Cable, Control Cables, Local Push Button Control Station with Emergency Stop Push Button, Isolators, Cable Trays, Cable Termination Kits and Accessories, Subgrade Earthing, and Equipment Earthing	Lot			
5.1.2	All instrumentation and control work as per the contract at intake and outfall system including DCS Controllers, IO units, instrumentations, flow meters, air bursting, shock chlorination system and chlorine dosing to intake pump discharge.	Lot			
5.1.3	Any other works (Items should be specified)	Lot			
	Sub-Total Item No. 5.1 (Sum of Item 5.1.1 to 5.1.3)				
5.2	Intake Pumping Station (400 MLD)				
5.2.1	All electrical works at Intake pumping station including but not limited to 11kV Motors, 11kV Switchgear, 11kV Soft Starters, 11kV Cables, 11/0.433 Transformers, LV Bus Ducts, Motor Control Center, LV Power Cable, Control Cables, Local Push Button Control Station with Emergency Stop Push Button, Cable Trays, Cable Termination Kits and Accessories, Subgrade Earthing System, Potential Gradient Earthing System, Lightning Protection System, and Equipment Earthing System	Lot			

Item No.	Description of Electrical & ICA Items Procurement, Supply, Installation/Erection, Testing and Commissioning for 2x200 MLD Plant	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
			1	2	3
5.2.2	All instrumentation control and automation (ICA) works as per the contract including DCS Controllers, IO units, instrumentations, pH, Temp, Chlorine, Conductivity, Turbidity, flowmeters, condition monitoring system etc. and all other analysers as per the contract	Lot			
5.2.3	Any other works (Items should be specified)	Lot			
	Sub-Total Item No. 5.2 (Sum of Item 5.2.1 to 5.2.3)				
5.3	Pre-treatment Chemical Systems (2x200 MLD)				
5.3.1	All electrical works at pre-treatment chemical system including but not limited to Motor Control Centers, Bus Ducts, Power Cables, Control Cables, Dosing Pumps, Mixers, Ventilation Fans, Isolators, Local Control Push Buttons with Emergency Stop, Watertight Flexible Conduits, Cable Trays, Cable Glands, and Equipment Earthing.	Lot			
5.3.2	All ICA works including instrumentation and automation as per the contract for all pre-treatment chemical dosing system	Lot			
5.3.3	Any other works (Items should be specified)	Lot			
	Sub-Total Item No. 5.3 (Sum of Item 5.3.1 to 5.3.3)				
5.4	Pre-treatment Process Units (2 x 200MLD)				
5.4.1	All electrical works including but not limited to LV Bus Ducts, Motor Control Centers, LV Power Cables, Control Cable, Cable Trays, Isolators, Local Push Button Station with Emergency Stop Push Button, Subgrade Earthing System, Equipment Earthing System, Chemical Dosing Pumps, Mixers, Sludge Scraper, Recirculation Pumps, Ventilation Fans, and Air Compressors	Lot			

Item No.	Description of Electrical & ICA Items Procurement, Supply, Installation/Erection, Testing and Commissioning for 2x200 MLD Plant	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
			1	2	3
5.4.2	All ICA works as per the contract for all pre-treatment process units including filter consoles, instrumentations, analysers, DCS controllers and IO units complete in all respect for auto operation.	Lot			
5.4.3	Any other works (Items should be specified)	Lot			
	Sub-Total Item No. 5.4 (Sum of Item 5.4.1 to 5.4.3)				
5.5	GDMF Backwash and RO Feed Tank (2 x 200 MLD)	Lot			
5.5.1	All electrical works including but not limited to 11kV Switchgear, Soft Starters, LV Bus Ducts, Motor Control Centers, LV Power Cables, Control Cable, Cable Trays, Isolators, Local Push Button Station with Emergency Stop Push Button, Subgrade Earthing System, Equipment Earthing System, Backwash Pumps, Air Scouring Blower, and Waste Disposal Pump, Ventilation Fans.	Lot			
5.5.2	All ICA works as per the contract for RO feed Tank	Lot			
5.5.3	Any other works (Items should be specified)	Lot			
	Sub-Total Item No. 5.5 (Sum of Item 5.5.1 to 5.5.3)				
5.6	RO Skids and CIP System (2 x 200 MLD)				
5.6.1	All electrical works including but not limited to 11kV Motors, 11kV Switchgears, 11kV Soft Starters, 11kV Cables, 11/0.433 Transformers, 11/0.69kV Transformers, LV Bus Ducts, Motor Control Centers, Filtered Water Pumps, Booster Pumps, High Pressure Pumps, Crane, CIP Pump, Flushing Pump, Cleaning Tank Mixer, Cleaning Pump, Air Compressor, Dryer Filter, Cooling Water Pump, Service Water System, and Permeate Water Pump, Ventilation Fans, LV Power Cable, Control Cables, Local Push Button Control Station with Emergency Stop Push Button, Cable Trays, Cable Termination Kits and Accessories, Subgrade Earthing	Lot			

Item No.	Description of Electrical & ICA Items Procurement, Supply, Installation/Erection, Testing and Commissioning for 2x200 MLD	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
	Plant		1	2	3
	System, Potential Gradient Earthing System, Lightning Protection System, and Equipment Earthing System				
5.6.2	All ICA works as per the contract at RO system, CIP tank, permeate tank, neutralization tank including instrumentations, flowmeters, pressure measurement, analysers such as chlorine, turbidity, Boron, conductivity, TSS, SDI, ORP and DCS IO units and Controllers etc. as per the contract.	Lot			
5.6.3	Any other works (Items should be specified)	Lot			
	Sub-Total Item No. 5.6 (Sum of Item 5.6.1 to 5.6.3)				
5.7	Post Treatment System (2 x 200 MLD)				
5.7.1	All electrical works including but not limited to 11kV Motors, 11kV Switchgears, 11kV Soft Starters, 11kV Cables, 11/0.433 Transformers, 11/0.69kV Transformers, LV Bus Ducts, Motor Control Centers, Local Push Button Control Station with Emergency Stop Push Button, Cable Trays, Cable Termination Kits and Accessories, Subgrade Earthing System, Potential Gradient Earthing System, Lightning Protection System, Equipment Earthing System, Limestone Filter Feed Pumps, Degassing Air Blowers, Air Scouring Blower, Lime Stone Unloading System, Lime Stone Recharging System, Waste Disposal Pump, Process Water Pump, Carbon Dioxide Plant, Chlorine Evaporator, Overhead Crane, Recarbonation Tower Feed Pump, and Ventilation Fans.  All ICA works as per the contract at CO <sub>2</sub> system and Limestone filters and	Lot			
5.7.2	Caustic system including DCS Controllers, IO units, Instrumentation flowmeters, pressure, level measurements, analysers such as chlorine, conductivity, hardness, pH etc.	Lot			
5.7.3	Any other works (Items should be specified)	Lot			
	Sub-Total Item No. 5.7 (Sum of Item 5.7.1 to 5.7.3)				

Item No.	Description of Electrical & ICA Items Procurement, Supply, Installation/Erection, Testing and Commissioning for 2x200 MLD Plant	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
			1	2	3
5.8	Product Water Tanks, CWR and Outfall Tank				
5.8.1	All electrical works including but not limited to Motor Control Center, Power Cable, Control Cable, Local Control Push Button Station with Emergency Stop, Subgrade Earthing System, Equipment Earthing System, Potable Water Delivery Pump, Overhead Crane, NaClO Dosing Pump, and Cathodic Protection.	Lot			
5.8.2	All ICA works as per the contract at product water tanks, CWR and outfall tanks.	Lot			
5.8.3	Any other works (Items should be specified)	Lot			
	Sub-Total Item No. 5.8 (Sum of Item 5.8.1 to 5.8.3)				
5.9	Waste /Sludge Conveyance and Treatment System				
5.9.1	All electrical works including but not limited to Motor Control Centers, LV Power Cables, Control Cables, Cable Trays, Subgrade Earthing System, Equipment Earthing System, Isolators, Local Control Push Buttons with Emergency Stop, Submersible Mixers, Sludge Scrapers, Sludge Extraction Pump, Sludge Belt Press, Flocculator, Wash Water Pump, Screw Conveyor, Air Compressor, and Ventilation Fans.				
5.9.2	All ICA works including flowmeters and analysers as per the contract at sludge balance tank, thickeners, sludge holding tanks and BFP building including polymer ejector loading system	Lot			
5.9.3	Any other works (Items should be specified)	Lot			
	Sub-Total Item No. 5.9 (Sum of Item 5.9.1 to 5.9.3)				
5.10	230/110/11kV GIS Substation				

Item No.	Description of Electrical & ICA Items Procurement, Supply, Installation/Erection, Testing and Commissioning for 2x200 MLD	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
	Plant		1	2	3
5.10.1	230kV Incoming Gantry Area including Outdoor Termination Units and Steel Structures				
5.10.2	230kV Gas Insulated Switchgear Double Bus Bar 4000A, 50Hz, 3 Ph, 50kA in 3 secs. as per Key Single Line Diagram	Lot			
5.10.3	110kV Gas Insulated Switchgear Double Bus Bar 3150A, 50 Hz, 3 Ph, 40kA in 3 secs. As per Key Single Line Diagram	Lot			
5.10.4	2 Nos. 230/110/33kV 150 MVA Auto Power Transformers with ONAN/ONAF Cooling and Vector Group YNa0d1 as per Key Single Line Diagram	Lot			
5.10.5	2 Nos. Earthing Transformer 33/0.433kV with ONAN Cooling and Vector Group ZNyn11 as per Key Single Line Diagram	Lot			
5.10.6	4 Nos. 110/11kV 50MVA Auto Power Transformer with ONAN/ONAF Cooling and Vector Group YNd5 as per Key Single Line Diagram	Lot			
5.10.7	4 Nos. Earthing Transformer 11/0.433kV with ONAN Cooling and Vector Group ZNyn11 as per Key Single Line Diagram	Lot			
5.10.8	Metering and Protection Relays including CTs and VTs for 230kV &110kV GIS, 33kV Outdoor Circuit Breakers and Isolators and 11kV Switchgears, Auto Power Transformers, and Earthing Transformers	Lot			
5.10.9	230kV & 110kV XLPE Cables including Cable Plug-in Modules and Cable Sealing ends	Lot			
5.10.10	33kV & 11kV XLPE Power Cables including Termination Kits and Accessories	Lot			
5.10.11	33kV Outdoor Type Vacuum Circuit Breakers and Isolators	Lot			
5.10.12	11kV Outdoor Type Vacuum Circuit Breakers and Isolators	Lot			

Item No.	Description of Electrical & ICA Items Procurement, Supply, Installation/Erection, Testing and Commissioning for 2x200 MLD Plant	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
	1 tant		1	2	3
5.10.13	II ightning Protection System	Lot			
5.10.14	11kV Switchgear Indoor Type including Metering and Protection Relays as per Key Single Line Diagram	Lot			
5.10.15	LV Switchboards, 110V & 48V DC Distribution boards, and Batteries	Lot			
5.10.16	Substation Automation System and SCADA System	Lot			
5.10.17	Fiber Optic Cables, LV Power Cables, ELV Cables, and Control Cables	Lot			
5.10.18	Lighting and Small Power System, HVAC System, CCTV System, Telecommunication and LAN System	Lot			
5.10.19	Fire Alarm System, FM200 System, and Deluge Water Spray System	Lot			
5.10.20	Overhead Travelling Crane for 230kV & 110kV GIS Rooms	Lot			
5.10.21	Potable Water System and Drainage System	Lot			
	Sub-Total Item No. 5.10 (Sum of Item 5.10.1 to 5.10.21)				
5.11	Control System				
5.11.1	All DCS hardware works as per the Contract including Controllers, Remote IO, Operator Stations, DCS Control Servers, Communication system, CMMS/ Optimization servers, FOC, Display units, GPS, Rack units, Large Wall Screen, Printers, Routers, DCS ergonomic Operator Control desks, configuration Laptops, Reporting system, any peripherals. Etc	Lot			
5.11.2	All DCS software works as per the contract including database engineering, configuration and programming for Operating System,	Lot			

Item No.	Description of Electrical & ICA Items Procurement, Supply, Installation/Erection, Testing and Commissioning for 2x200 MLD Plant	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
	Historian, CMMS, Optimization, Cybersecurity, Antivirus, Instrumentation Management, Reporting system. Etc.				
5.11.3	Any other works (Items should be specified)	Lot			
	Sub-Total Item No. 5.11 (Sum of Item 5.11.1 to 5.11.3)				
5.12	Miscellaneous				
5.12.1	Electrical and ICA works at sewage treatment system	Lot			
5.12.2	All electrical and ICA system at the administrative building and all other buildings	Lot			
5.12.3	All plant lighting system including plant earthing and lightning protection system	Lot			
5.12.4	The UPS and Diesel Generators as per contract	Lot			
5.12.5	Other Miscellaneous Equipment / Items / System not mentioned above but as required in Employers Requirement Part-II (Items should be specified)	Lot			
	Sub-Total Item No. 5.12 (Sum of Item 5.12.1 to 5.12.5)				
5.13	Bidders shall list here details of any additional items required for a complete electrical and ICA system for smooth and automatic operation of the 400 MLD plant				
	Sub-Total Item No. 5.13 (Sum of Items therein)				
	Total Schedule 5 (Sum of Sub-Totals of Item No. 5.1 to Item No. 5.13)				
	Total carried forward to Schedule No. 8				

Chennai Seawater Desalination Project (
---

Part-IV: Price Schedule

Signature of Bidder

Name & Designation

Company and Seal

#### **Schedule 6: Miscellaneous Works**

This Schedule shall include, but not limited to the following items to deliver the works from supply to commissioning fit for the purpose as per the Contract.

	Item Description of Miscellaneous Works for Procurement, Supply, Installation/Erection, Testing and Commissioning for 2x200 MLD Plant	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
			1	2	3
6.1	Chemical Laboratory Items as per schedule and required. (complete Schedule 12)	Lot			
6.2	Workshop items as per schedule and required. (complete Schedule 13)	Lot			
6.3	Heating, Ventilation and Air conditioning systems in all buildings/ structures as required and specified in the contract	Lot			
6.4	Firefighting system - fire detection and protection system in all building and covered places - including pumps, pipes, valves, and allied items as per requirement and specifications in the contract	Lot			
6.5	Security and Surveillance system at the plant including gate security, plant monitoring and access system as per requirement and specifications in the contract	Lot			
6.6	Any other works required to operate the 400 MLD DSP smoothly meeting the contract requirements such as vehicles for the Employer. FAT, temporary site office etc. (Items should be specified)	Lot			
	Total Schedule 6 (Sum of Sub-Totals of Item No. 6.1 to Item No. 6.6)  Total carried forward to Schedule No. 8				

Signature of Bidder

Name & Designation

Company Name and Seal

Chennai Seawater Desalination Project (I)

Part-IV: Price Schedule

# **Schedule 7: Process Proving**

Item No.	Item Description	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
			1	2	3
7	Three months of Process Proving Test Period				
7.1	Power usage (energy charges @ INR 6.35/ kWh and demand charges @ INR 350 / kVA / month )	Lot			
7.2	Chemical Usage	Lot			
7.3	Transportation of Sludge	Lot			
7.4	Manpower	Lot			
	Total Schedule 7 (Sum of Sub-Totals of Item No. 7.1 to Item No. 7.4)				
	Total carried forward to Schedule No. 8				

Signature of Bidder

Name & Designation

Company Name and Seal

# Schedule 8: Summary of CAPEX Price

Schedule No.	Item Description	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
		1	2	3
1	Surveys & Investigations, Design, Drawings and Documentation			
2	Intake and Outfall Pipeline Works			
3	Civil Works			
4	Mechanical Works			
5	Electrical and ICA Works			
6	Miscellaneous Works			
7	Process Proving			
GRAND T	COTAL OF CAPEX PRICE (Sum of Schedule 1 to 7)			

Signature of Bidder Name & Designation Company Name and Seal

# **Schedule 9: Operation and Maintenance Price**

Item No.	Item Description	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
110.			1	2	3
1	First year				
1.1	Variable Price including chemicals and others.				
1.1.1	Chemicals Consumption during O&M period (complete the Schedule-14)	Lot/ year			
1.1.2	Any other variable cost (attached details separately)	Lot/ year			
	Variable Price (Sum of Items 1.1.1 to 1.1.2)				
1.2	Fixed Price including manpower cost, asset replacement cost, membrane cost and administrative cost				
1.2.1	Manpower during O & M period (complete the Schedule 15)	Lot/ year			
1.2.2	List of Asset Replacement and Spare Parts over 20 years (complete the Schedule 16)	Lot/ year			

Item No.	Item Description	Unit	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
140.			1	2	3
1.2.3	List of Membrane Replacement over 20 years (complete the Schedule 17)	Lot/ year			
1.2.4	Administrative cost (attach details separately)	Lot/ year			
1.2.5	Routine Maintenance (attach details separately)	Lot/ year			
1.2.6	Any other fixed cost (such as Fuel, Vehicle maintenance, sludge disposal, Environmental monitoring and statutory compliance reporting etc. attach details separately)				
	Fixed Price (Sum of Items 1.2.1 to 1.2.6)				
1.3	O & M Price (Variable Price + Fixed Price) - First year				

Note: - Fixed Price should not be more than 30% of the O&M Price for each year. For Sludge disposal, the Bidder shall provide the per unit rate for disposal beyond 20 km.

Signature of Bidder

Name & Designation

Company Name and Seal

Note: Similar Sheets are to be filled for the rest of the year from  $2^{\text{nd}}$  year to  $20^{\text{th}}$  year.

Chennai Seawater Desalination Project (I)

### Schedule 10: Summary of Operation & Maintenance Price

Year	Item Description	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)	
		1	2	3	
1.	1 <sup>st</sup> Year O&M Price				
2.	2 <sup>nd</sup> Year O&M Price				
3.	3 <sup>rd</sup> Year O&M Price				
4.	4 <sup>th</sup> Year O&M Price				
5.	5 <sup>th</sup> Year O&M Price				
6.	6 <sup>th</sup> Year O&M Price				
7.	7 <sup>th</sup> Year O&M Price				
8.	8 <sup>th</sup> Year O&M Price				
9.	9 <sup>th</sup> Year O&M Price				
10.	10 <sup>th</sup> Year O&M Price				
11.	11 <sup>th</sup> Year O&M Price				
12.	12 <sup>th</sup> Year O&M Price				
13.	13 <sup>th</sup> Year O&M Price				
14.	14 <sup>th</sup> Year O&M Price				
15.	15 <sup>th</sup> Year O&M Price				
16.	16 <sup>th</sup> Year O&M Price				
17.	17 <sup>th</sup> Year O&M Price				
18.	18 <sup>th</sup> Year O&M Price				
19.	19 <sup>th</sup> Year O&M Price				
20.	20 <sup>th</sup> Year O&M Price				
TOTA	AL O&M PRICE (Total Carried out to Schedule 11)				

Signature of Bidder

Name & Designation

Company and Seal

Schedule 11: Grand Summary (Summary of CAPEX Price & Summary of Operation & Maintenance Price)

Schedule	Description of Works	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
1	Surveys & Investigations, Design, Drawings and Documentation	1		
2	Intake and Outfall Pipeline Works			
3	Civil Works			
4	Mechanical Works			
5	Electrical and Instrumentation, Control and Automation (ICA) Works			
6	Miscellaneous Works			
7	Process Proving			
9	Operation and Maintenance Price			
GRAND TO	OTAL OF SCHEDULE (Sum of Schedule 1, 2, 3, 4, 5, 6, 7 & 9)			

Signature of Bidder Name & Designation Company Name and Seal

# **Schedule 12: Chemical Laboratory Items**

Item No.	Item Description	Unit	Qty	Base Price in Local Currency (INR)	Total Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Total Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)	Total Price in Foreign Currency (JPY)
		1	2	3	4=3x2	5	6=5x2	7	8=7x2
1	Electronic Balance	No.	4						
2	Bunsen Electric Heater	No.	4						
3	Magnetic Stirrer - 1MLH	No.	4						
4	Water bath with 6 to 8 concentric holes and discs, electrically heated	No.	2						
5	Muffle Furnace	No.	2						
6	Colour Comparator	No.	2						
7	Centrifuge system	Set	2						
8	Turbidity meter	No.	4						
9	Autoclave	No.	2						
10	Coagulation-Flocculation Simulator	No.	2						
11	COD Assembly	No.	2						
12	Distilled water plant	No.	2						
13	ORBECO Analytical System	No.	2						
14	ORBECO HELLIGE -975MP	No.	2						
15	Electric Oven	No.	2						
16	BOD Incubator	No.	2						
17	TDS meter	No.	4						
18	Spectrophotometer- UV-UIS Spectrophotometer Latest Unit	No.	2						

Item No.	Item Description	Unit	Qty	Base Price in Local Currency (INR)	Total Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Total Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)	Total Price in Foreign Currency (JPY)
		1	2	3	4=3x2	5	6=5x2	7	8=7x2
19	Potable kit for pH/ORP/Cond/TDS/ Temp/DO meters	No.	4						
20	Weight Balance	No.	4						
21	pH meter- pH Scan2	No.	4						
22	Refrigerator and Freezer, 500 lts capacity of approved make	No.	2						
23	Burette, Pipette, Flask	Set	50						
24	Measuring Cylinders (1000 ml, 500 ml, 200 ml, 100 ml, 50 ml, 25 ml)	Set	6						
25	Chlorine analyzer (comparator)	No.	4						
26	Conductivity meter	No.	4						
27	Mercury Ioniser	No.	2						
28	Dissolved Oxygen Meter	No.	4						
29	Colony counter	No.	2						
30	Membrane Filtration Assembly	No.	2						
31	Binocular Microscope	No.	2						
32	Jar test apparatus	No.	2						
33	Sampling Bottles (Reagent Bottles of 250 ml Capacity)	No.	100						
34	Wire Baskets	No.	10						
35	Suction Flask (1litre capacity)	No.	4						
36	TOC analyser – High Temp Combustion type	No.	1						

Item No.	Item Description	Unit	Qty	Base Price in Local Currency (INR)	Total Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Total Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)	Total Price in Foreign Currency (JPY)
		1	2	3	4=3x2	5	6=5x2	7	8=7x2
37	All types of laboratory glassware, accessories and other consumables and reagents for minimum two years requirement.	No.	Lot						
	Total Schedule 12 (Sum of Items 1 to 37) (To be carried to Schedule 6 – Miscellaneous Works)								

Signature of Bidder

Name & Designation

Company Name and Seal

# **Schedule 13: Workshop Items**

Item No.	Item Description	Qty	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
1	Heavy-duty high-speed lathes, 250 mm centre height, 1500 mm between centres including all features as per the specifications	1			
2	Heavy-duty high-speed lathes, 200 mm centre height, 1500 mm between centres including all features as per the specifications	1			
3	Heavy duty high speed vertical lathes, 2000 mm table diameter, working piece diameter 2300 mm, working piece height 1400 mm, working piece weight 20000 kg, with accessories	1			
4	Horizontal boring, drilling and milling machine, work spindle dia.100 mm, self-acting traverse of spindle at one setting 700 mm, with all features as per the specifications	1			
5	Surface grinding machine wet grinding, grinding wheel diameter/ width 250/25 mm, distance table to centre of spindle approx. 500 mm, table clamping area 900 x 250 mm, steeples adjustable including electrical equipment with motor and standard accessories	3			
6	Column grinder, with 2 wheels 300 x 40 x 76 mm for wet grinding, left hand side with normal rest, right hand side with adjustable workpiece support table and angle stop, with all features as per the specifications	2			
7	Universal milling machine, table size 1300 x 400 mm, steeples feed drive in all three table directions, longitudinal travel of table 1000 mm, cross travel of table 340 mm with all features as per the specifications	2			
8	Vertical milling machine, table size 1900 x 400 mm, steeples feed drive in all three table directions, integrated automatic lubricating system, cooling system, main spindle drive, motor protection switch, controls integrated on panel, accessories.	1			
9	Heavy-duty high-speed shaping machine, 725 mm ram stroke, 725 x 340 mm table size, shaping width 600 mm, complete with electric motor equipment, automatic vertical feed	1			

Item No.	Item Description		Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
	of the tool holder, main switch, motor protection switch, rotary concentric machine vice, with standard accessories.		1	2	3
10	Screw threading machine, with solid steel frame, including pole- changing 3-phase motor for pipe and whitworth thread from 1/4 to 2", metric threads M6 to M52, with motor protection switch and standard accessories.	1			
11	Heavy duty power hacksaw, fully hydraulic 4 stroke, cutting range in round material 225 mm, for metering from 450 mm, complete with electric motor equipment, stock support 500 mm high with heavy material Toller, accessories.	2			
12	Heavy duty circular column drilling machine, drilling capacity in steel up to 35 mm, in cast iron up to 45 mm, 350 mm column-spindle distance, column diameter approx. 160 mm, stepless, with at least.3 kW electric motor, motor protection switch, coolant supply pump, accessories.	1			
13	Bench drilling machine, drilling capacity in steel up to 10 mm, radius 200 mm, with high-capacity high-speed chuck to 10 mm, adjustable rectangular table, drilling depth 60 mm, column diameter 70 mm, base plate 170 x 170 mm, complete with electrical equipment and motor, motor protection switches and standard accessories.	2			
14	Electric pipe bender, complete with all necessary tooling required for cold bending heavy gauge steel pipe of up to 100 mm inside diameter to the smallest radic possible, limited only by the pipe bore and wall thickness, without flattening.	2			
15	Universal folding press, for hand operation, including base frame, for 3 mm plate thickness, 2000 mm working width, 45° angle bar, 3 mm rad. round bar, steel rail for the bending beams, accessory holders with standard accessories.	2			
16	Combined plasma welding and metal cutting set, cutting range from 2 to 25 mm in steel, provisions for connecting to argon, nitrogen or hydrogen gas bottles complete with welding and manual cutting torches, pressure regulators and one year's supply of welding rods and gas bottles.	2			

Item No.	Item Description		Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
17	Mobile work benches 1500 x 700 mm surface area, suitable for containing one set of mobile work bench tools each.	2			
18	Steel tool cupboards 500 x 500 x 1000 mm high, including 125 mm leg height, with upper steel drawer and two removable trays, door latch for padlock, including lock.	4			
19	Steel tool cupboards with double doors, 1000 x 500 x 1000 mm high including 125 mm leg height, with centre partition, each side separately lockable with two steel drawers and two removable trays, door latches for padlocks, including padlocks.	6			
20	Work benches with 1500 x 700 x 50 mm plywood top, backboard, angle iron supporting frame, one steel plate drawer, with safety lock and two keys, one shelf underneath of extra strong construction, with six (6) all-steel parallel vices, 150 mm jaw width with bolts for through attachment to the benches.	10			
21	Vertical drilling machine	2			
22	Hacksaw machine	2			
23	Bench Grinder	2			
24	Miscellaneous items and hand tools with safety equipment	Lot			
25	Toolboxes	10			
26	Portable Noise level tester	4			
27	Portable vibration tester	4			
28	Magnetic base dial gauge	4			
29	Portable temperature meter	4			
30	Filler gauge	4			
31	Precision spirit level	4			
32	415V, 3 phase, 50hz, 40kVA portable DG set (trolley mounted) including all necessary metering & protection unit, battery, manual control panel, plug & socket, etc., with cable and accessories. Acoustic enclosure which complies with all environmental regulations shall be included as a part of the supply.	2			

Item No.	Item Description	Qty	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
33	Toolbox with all necessary tools fixed spanner, ring spanners, screwdrivers, adjustable jaw spanners, etc.	5			
34	Hand trolley (500kg capacity)	4			
35	Tripod with chain pulley blocks of 1 Ton capacity (6.0m legs)	4			
36	Welding set, 400 amp, three-phase regulator type, air-cooled, wheel mounted with 15 m welding cable, 2 m. welding cable for earthing, one welding holder, one welding screen with glass and 3 cable lugs, one pair hand gloves and one wire brush	2			
37	Portable hand drill (heavy duty) of capacity 13 mm to 23 mm with ½" drill chuck but with drill bits and drill stand	4			
38	Tong tester, 1000 Amp	4			
39	Hand crimping tool with dies suitable for cable joining up to 95 sq. mm.	2			
40	Hydraulic crimping tool, suitable for cable joining from 25 to 400 sq. mm.	4			
41	Hydraulic jack, 5 Ton capacity	4			
42	De-watering pump sets of 5 kW with 50 meters hose pipe	4			
43	Motorized and handle operated insulation resistor tester, 5 kV (multi-range setting), with battery pack	4			
44	Handle-operated insulation resistor tester - 1000 Volts	4			
45	Megger, 1000 volt	2			
46	Megger, 5000 volts (motorized)	2			
47	Insulating oil tester and filter	2			
48	Hand grinder (Angle 7")	2			
49	Clamp-on Digital Meter (0 - 1000 Amperes)	2			
50	Multi-meter (Digital)	2			
51	Micro-Ohm meter	2			
52	Portable vacuum cleaner/blower (industrial type)	4			

Item No.	Item Description	Qty	Base Price in Local Currency (INR)	Base Price in Foreign Currency (USD)	Base Price in Foreign Currency (JPY)
53	Aluminium folding ladder - 8 meters	4			
54	4 terminal Earth Tester (digital)	4			
55	Rubber gloves (110 kV rating)	12			
	Total Schedule 13 (Sum of Items 1 to 55) (to be carried to Schedule 6 – Miscellaneous Works)				

Signature of Bidder Name & Designation Company Name and Seal

Part-IV: Price Schedule

Schedule 14: Chemical Consumption during Operation & Maintenance Period

Item No.	Description of Chemical Consumption (Yearly) during O&M Period	Unit (as supplied)	Guaranteed Quantity	Base Price (INR)	Total Price in Local Currency (INR)	Base Price (USD)	Total Price in Foreign Currency (USD)	Base Price (JPY)	Total Price in Foreign Currency (JPY)
		1	2	3	4=3x2	5	6=5x2	7	8=7x2
1	Hypochlorite for Shock Chlorination	Tons / year							
2	Hypochlorite for Pre-Chlorination	Tons / year							
3	Sulfuric acid for Pre-Chlorination	Tons / year							
4	FeC13 solution dosing (40%)	Tons / year							
5	Anionic Polymer dosing for flocculation (Food grade)	Tons / year							
6	Cationic Polymer for Thickener	Tons / year							
7	Cationic Polymer for BFP (Non-Food grade)	Tons / year							
8	Antiscalant	Tons / year							
9	Sodium Bisulphite	Tons / year							
10	Any other chemical for biofouling control	Tons / year							
11	CO <sub>2</sub> for remineralization	Tons / year							
12	CaCO3 for remineralization	Tons / year							
13	Hypochlorite for Post Chlorination	Tons / year							
14	NaOH for pH adjustment pre/post RO system	Tons / year							
15	Citric Acid for CIP	Tons / year							
16	HCl for CIP & Neutralization	Tons / year							
17	NaOH for CIP & Neutralization	Tons / year							
18	Any other Chemicals	Tons / year							
	Total Schedule 14 (Sum of Items 1 to 18) (to be carried to Schedule 9)								

Signature of Bidder Name & Designation Company Name and Seal

# Schedule 15: Manpower during Operation & Maintenance Period

Item No.	Designation of Manpower during O&M Period	No. of Staff	Basic Salary/ year (INR)	Other Benefits/year (INR)	Income Tax / year (INR)	Gross Salary (INR)/Annum
1	2	3	4	5	6	7=4+5+6
1.	Plant Manager					
2.	Sr. Operation Manager					
3.	Operation Manager/ Shift-in-charge					
4.	Maintenance Incharge					
5.	Maintenance Personnel					
6.	SCADA Operator					
7.	Field Operator					
8.	Admin Staff					
9.	Chemist					
10.	Lab Assistant					
11.	Helpers					
12.	Safety Officer					
13.	Security Guards					
14.	Drivers					
15.	Gardener/Cafeteria cleaning					
16.	Any other staff					
	Total Schedule 15 (Sum of Items 1 to 16) (to be carried to Schedule 9)					

Signature of Bidder Name & Designation Company Name and Seal

Schedule 16: List of Asset Replacement and Spare Parts Over 20 years

Item No.	Item Description	Guaranteed Quantity	Base Price (INR)	Total Price in Local Currency (INR)	Base Price (USD)	Total Price in Foreign Currency (USD)	Base Price (JPY)	Total Price in Foreign Currency (JPY)
		1	2	3=2x1	4	5=4x1	6	7=6x1
	Total Schedule 16 (to be carried to Schedule 9)							

Part-IV: Price Schedule

Note: Total price in this Schedule 16 shall be equal to the additional of Asset Replacement Costs of Schedule-9 over 20 years. Bidders may provide separate sheet for every year during O&M period of 20 years.

Signature of Bidder Name & Designation Company Name and Seal

Chennai Seawater Desalination Project (I)

Schedule 17: List of Membrane Replacement over 20 years

Item No.	Item Description	Guaranteed Quantity	Base Price (INR)	Total Price in Local Currency (INR)	Base Price (USD)	Total Price in Foreign Currency (USD)	Base Price (JPY)	Total Price in Foreign Currency (JPY)
1.	RO membrane (type -1)	1	2	3=2x1	4	5=4x1	6	7=6x1
2.	RO membrane (type -2)							
3.	Micron Cartridge Filters							
4.								
5.								
	Total Schedule 17 (to be carried to Schedule 9)							

Note: Total price in this Schedule 17 shall be equal to the addition of Membrane Replacement Costs of Schedule-9 over 20 years. Bidders may provide separate sheet for every year during O&M period of 20 years.

Signature of Bidder

Name & Designation

Company Name and Seal

#### **Schedule 18: Payment Terms**

Payment Schedule shall be regulated as under:

All payment shall be done deducting the Retention Money as per contractual provisions.

Surve	Survey & Investigations, Designs, Drawings and Documentation						
Sl. No.	Description	%age Payment					
1	Against submission of complete Reports, Designs, Drawings and Documents.	30%					
2	Against Employer's Representative consent with comment category of submissions	20%					
3	Against final consent of Employer's Representative on the above submissions	40%					
4	Against submission of complete "As-Built" drawings	10%					

Intak	Intake Outfall Pipeline Works						
Sl. No.	Description	%age Payment					
1	Supply of intake and outfall HDPE pipe, Heads and Diffusers at site	20%					
2	Complete installation of pipeline, Heads and Diffusers. Payment based on progress achieved in laying of the pipeline on a pro-rata basis	60%					
3	Completion of satisfactory Testing & Commissioning	15%					
4	On successful Process Proving Test and issue of Commissioning Certificate.	5%					

Civil	Civil Works					
Sl. No.	Description	%age Payment				
1	Supply of civil items and Completion of Sub-structure/piling/raft up to plinth level on pro-rata basis.	20%				
2	Completion of super structure on pro-rata basis.	40%				
3	Completion of allied items such as handrail, painting, epoxy coat etc. on pro-rata basis.	10%				
4	Completion of satisfactory Testing & Commissioning	20%				
5	On successful Process Proving Test and issue of Commissioning Certificate.	10%				

This mode of payment of Works will be applicable only for concrete works such as Tanks, retaining walls & Buildings but not for Road Works, Boundary Walls Works, Landscape works for which payment will be done on measurement basis.

Mec	Mechanical Works, Electrical Works & ICA Works					
Sl. No.	Description	%age Payment				
1	Receipt of material on site and submission of complete documentation thereof.	60%				
2	Completion of Erection on pro-rata basis	10%				
3	Completion of satisfactory Testing & Commissioning	20%				
4	On successful Process Proving Test and issue of Commissioning Certificate.	10%				

Miso	Miscellaneous Works						
Sl. No.	Description	%age Payment					
1	Receipt of material on site and submission of complete documentation thereof.	50%					
2	Completion of Erection on pro-rata basis.	20%					
3	Completion of satisfactory Testing & Commissioning	20%					
4	On successful Process Proving Test and issue of Commissioning Certificate.	10%					

Proc	Process Proving						
Sl. No.	Description	%age Payment					
1	Successful completion of First Month	25%					
2	Successful completion of Second Month	25%					
3	Successful completion of Third Month	25%					
4	After issue of Commissioning Certificate.	25%					